

**TENDER FOR CIVIL WORKS AT NCA COLLEGE &
HOSTELS**

Sealed tenders are invited for

1. Laying of Soling at College Parking
2. Miscellaneous Civil Work at NCA Hostel

From the reputed firms/companies registered with sale tax department for said work Detail specifications are available in tender's document. Tenders Document may be collected from Project Director Office from the college on cash payment of Rs, 1000/- each (nonrefundable) as a tender document fee. Tenders Documents may be dropped in Tender Box placed in PD Office on 25.08.2015 at 11:00 AM along with 2% Earnest Money in favour of Principal -NCA. The tender will be opened by the College Works Committee at 11.30 A.M on the same day in the presence of the interested contractors. The title of the tender should be clearly mentioned at the top of the envelope. The undersigned reserves the right to accept or reject any or all tenders under PPRA rules.



Principal

National College of Arts

4-shahrah -e- Qaid-e-Azam

Lahore.

**SPECIFICATIONS FOR BRICK SOLING AT REAR SIDE PARKING LOT,
NATIONAL COLLEGE OF ARTS, LAHORE.**

Sr.	Description	Unit	Rate	Quantity	Amount
1	Excavation in foundation for brick work, complete with leveling, dressing and compacting etc. as per design and directions of engineer in-charge.	Cft		100	
2	P/L 1 st class Burnt Brick masonry 13½" thick wall of approved quality laid in 1:4 CS mortar incl. leveling etc. complete in all respect as per design and directions of engineer in-charge.	Cft		200	
3	P/L 1 st class Burnt Brick soling on edge over 3" thick sand cushion including scrapping, leveling and compacting the earth as a base, then grouted with dry sand at NCA rear parking lot complete in all respect as per design and directions of engineer in-charge.	Sft		12,000	
4	P/L Existing old Burnt Brick soling on edge over 3" thick sand cushion including scrapping, leveling and compacting the earth as a base, then grouted with dry sand at NCA rear parking lot complete in all respect as per design and directions of engineer in-charge.	Sft		5,500	
				Total:	

CONTRACTOR'S NAME	
SIGNATURE	

NAME OF THE FIRM	
SIGNATURE, DATE & SEAL	
ADDRESS	

**SPECIFICATIONS FOR MISCL. REPAIR WORKS AT NCA HOSTELS,
NATIONAL COLLEGE OF ARTS, LAHORE.**

Miscellaneous Civil Works at NCA Hostels					
Sr.	Description	Unit	Rate	Quantity	Amount
1	Dismantling existing 1½" thick roof tile and removing mud then relaying 1½" thick brick tiles laid, grouted in 1:2 cement & marble powder over 1" thick layer of mud mixed with bhoosa over 4" average thick compacted earth over a layer of heavy duty polythene sheet over a layer of hot bitumen 30/40 @ 0.5 lbs/ft² over existing roof etc. complete in all respect and carrying out proper ridge and maintaining slope of NCA boys & girls hostel as per design and directions of engineer in-charge.	Sft		17,800	
2	P/L 2'x2' khurras P.C.C 1:2:4 cement: Sand (Chenab): stone crush finished with cement surkhi of NCA hostels roof as per design and directions of engineer in-charge.	Each		25	
3	Replacing damaged wooden rafters of existing NCA boy's hostel roof as per design and directions of engineer in-charge.	Each		5	
4	P/F rainwater down uPVC pipe 4" dia popular or equivalent brand on roof complete incl. elbow, bends, shoes, clamps etc. in all respect as per existing design of NCA boys hostel building and sample approved by engineer in-charge.	Rft		600	
5	P/Making corner gola 3"x3" on roof with 1:3 CS Mortar of NCA boys & Girls hostel roof complete in all respect as per design and directions of engineer in-charge.	Rft		2,160	
6	Repair and treatment of Fiber glass Skylights of NCA Girls Hostel	Each		04	
7	P/L Existing old Burnt Brick soling on edge over 3" thick sand cushion including scrapping, leveling and compacting the earth as a base, then grouted with dry sand at NCA rear parking lot complete in all respect as per design and directions of engineer in-charge.	Sft		8,700	
				Total:	

CONTRACTOR'S NAME	
SIGNATURE	

NAME OF THE FIRM	
SIGNATURE, DATE & SEAL	
ADDRESS	